



# दिल्ली मेट्रो रेल कॉर्पोरेशन लिमिटेड DELHI METRO RAIL CORPORATION LTD.

(भारत सरकार एवं दिल्ली सरकार का संयुक्त उपक्रम)  
(A JOINT VENTURE OF GOVT. OF INDIA AND GOVT. OF NCT DELHI)

डी.एम.आर.सी/20/II-186/2020/VOL-XIII/E 12703/2163

दिनांक - 04.01.2021

## WORK EXPERIENCE CERTIFICATE (FOR COMPLETED WORKS)

The Certificate supersedes earlier issued work experience certificate (For Completed works), No. DMRC/20/II-186/2007/V, dated 14.06.2019.

1	Name of work and contract no	Contract No. NCDD-O1: Engagement of detail designconsultant DDC for Civil, Architectural and buildingservices including E&M works for Noida-Greater NoidaCorridor
2	LOANo. & Date	DMRC/20-III/222/2014 dated 09/04/2015
3	Name of the contractor and address	M/s. AYESA Ingenieria YArquitectura, S.A.U(AYESA)56, Indo Asia House, Industrial Area Sector-44, Gurgaon - 122002
4	Joint Venture/Consortium along with %shares of each member	N/A
5	Contract value	
	1) Original Contract value	INR11,96,53,623
	2) Revised/Final Contract Value	INR 11,99,83,623
	3)Value of actually executed work(as on date of issue ofcertificate Le. value paid till the last running bill/final bill)	INR 11,79,81,917
6	Stipulated Date of commencement of work	09/04/2015
7	Stipulated date of completion	08/04/2017
8	Actual date of completion	30/06/2018
9	Details of E.O.T	1 <sup>st</sup> Extension Of Time: Given upto 30/06/2018 without LD
10	Liquidated Damages levied for delay (indicate amount), if any	N/A
11	Scope of the works Broad activities to be mentioned	<b>21 Elevated Stations:</b> <ul style="list-style-type: none"> <li>• Structural detail design</li> <li>• Architectural detail design (includinglandscaping, Property development, traffic integration and system integration)</li> <li>• Performing detailed designs for building works,like the fitting out of stations with architecturalfinishes and services including illuminations, lifts,escalators, water supply, drainage, power supply,fire detection and</li> </ul>



		<p>suppression and public telephones for complete station building.</p> <ul style="list-style-type: none"> <li>• Proof checking of design of Pre-Engineered building submitted by PEB contractor.</li> <li>• The stations have an approximate built-up area of 123186 m<sup>2</sup></li> </ul> <p><b>Depot:</b></p> <ul style="list-style-type: none"> <li>• Detail design of depot viz staff quarters(including tender document), OCC building, compound wall and all other ancillary buildings or architectural and structural components.</li> <li>• Depot includes 16 stabling lines (6 covered and 10 uncovered), 915 m test track, 6 lines in inspection bay, 4 lines in maintenance track, 1 line in cleaning shed, shunting area 264 nos. staff quarters and 1 no administration building(including OCC and DCC)</li> <li>• Proof checking of design of pre-engineered building submitted by the PEB contractor.</li> <li>• The built area is of 70000 m<sup>2</sup> and the whole area of the compound is 260000 m<sup>2</sup></li> </ul> <p><b>Viaduct:</b></p> <ul style="list-style-type: none"> <li>• Proof checking of structural design and scheme of construction suggested by the DMRC for C/U shaped superstructure for which good for construction drawing were also prepared.</li> <li>• Proof checking of structural design for viaduct substructure including pile foundation, precast pier cap, cast in situ cantilever and portal type pier caps.</li> <li>• Viaduct length 26.7 km</li> </ul>
12	Status of work along with overall % progress achieved till date	Physical progress - 100% Financial Progress- 100%
13	Overall performance	SATISFACTORY

The certificate is issued on the request of M/S. AVESA Ingenieria Y Arquitectura, S.A.U (AYESA) for Business Development.



*04/01/2020*

(ओमवीर सिंह सैनी)

महाप्रबंधक / योजना

दिल्ली मेट्रो रेल कॉर्पोरेशन की ओर से

Email: - [planningdmrc@gmail.com](mailto:planningdmrc@gmail.com)