

Contract CC-116: Design, fabrication, supply and erection of pre- engineering steel roof structure for six elevated stations viz., Noida Sector -34, Sector -52, Sector-61, Sector -59, Sector -62 and Electronic City of Noida City Centre to Sector -62 Corridor of Phase –III of Delhi MRTS Project.

Sr. No.	Pre – Bid Queries	Reply by DMRC	Remarks
Bidder-1			
1.	Provide drawings for FOBs with length, width and height details. (Please clarify scope)	The length of FOB will be as per site conditions. width and height of FOB as per drawing. However the quantities will be executed as per BOQ. If there is any deviation in executed quantity, it shall be paid under approved variation.	
2.	Details for the stations are not complete. Please provide complete drawings for the same.	Detail of drawings of stations are being enclosed.	
3.	Drawings are given for two stations only. Please provide complete drawings of other stations also.	All six stations having similar design. Hence drawings for other stations are not required.	
4.	Drawings provided are not clear. Please provide auto cad drawings.	Legible copies of original tender drawings are being issued with Addendum no. 1. However, there is no change in tender drawings.	
5.	Solar Panel show in drawing. Please clarify Supply of solar panel in PEB scope or only load should be consider.	Supply of solar panels is not in the scope of PEB contractor. It is shown in the drawings only for the load calculations in design of roof portals.	

Bidder-2				
S. No.	Reference Clause	Clarification Required	Reply by DMRC	Remarks
1	Volume-3, Clause 2.1.1 A	Down take pipe - PI clarify scope. BOQ have no provision.	Down take pipe is not in the scope of PEB contractor. Hence there is no provision in BOQ. ADDENDUM is being issued.	
2	Volume-3, Clause 2.1.1 A - 2nd Para	Only Automatic submerged arc welding is permitted - MIG also to be allowed wherever reqd.	No change from tender condition.	
3	Volume-3, Clause 2.1.1 B	General arrangement drawing including bracing, sag rod.... PI considered GA drawing of all building only at tender stage.	Not agreed. All four points/ details have to be given at tender stage.	
4	Volume-3, Clause 2.1.1 D	Provision for fixing of E&M, OHE.... Scope to be clarified or we will provide hole only on structures for this provision.	You have to make provisions with fixing of E&M, Raceways, OHE, signalling / telecommunication equipments in the steel roof structure with the coordination of other interface agency and not only making holes.	

5	Volume-3, Clause 2.1, 2.2.1, 2.1.2, 2.1.3, 2.1.4	Interface work - Not relevant please clarify the scope.	It is clarified that in addition to subject work of PEB you have to work with coordination / consultation of other agency like Civil, E & M, Signalling and Traction power supply contractor etc. Clause -2.2.1 & 2.1.2: These clauses are self explanatory and do not require any further clarification. Clause: 2.1.3 (i) & 2.1.4: are being deleted.	
6	Volume-4, Clause 5.4	Anchor Bolt (Holding down bolt 8.8 Gr,) - This should be 4.6 Gr as per provision in DBR (Annex A-Vol-4)	Anchor bolts/ Holding down bolts shall be of class -8.8 confirming to IS: 3757 and IS: 6623. ADDENDUM is being issued.	
7	Volume-4, Clause 12.3	Grouting under base plate - Scope to be clarified, Should be scope of civil agency	Grouting under base plate is in the scope of PEB contractor.	
8	Volume-4, Clause 14.3	Paint System - Kindly change the paint system, in place of fire paint you are suggested to use Epoxy Primer, Epoxy MIO and Acrylic polyurethane with proper DFT (LMRC Specification)	No change in specification.	
9	Volume-4, Section-B, Point-4	Metal roof sheet specification is different from BOQ specification (like BMT 0.50 MM or 0.45M and crests 183-205mm c/c / 186-333mm c/c etc)	ADDENDUM is being issued.	

10	Volume-4, Section-B, Point-9	20 Year Guarantee - Should be as per approved vendor	No change in specification.	
11	Volume-4, Section-B, Point-10	Rain water gutter 0.50mm BMT - Should be similar to roof sheet metal (0.45MM BMT)	ADDENDUM is being issued.	
12	Volume-4, Annexure A, Design Basis Report - Cl. 4.2.2.3, 4.5.1	Material handling loads supported on structures..... PI confirm	No material handling loads supported on structures except OHE dropdown arm.	
13	Volume 1 clause No. 1.1.2 Key Details- Date & time of Submission of Tender online	As various details and documents required to be submitted along with this tender and we finding it difficult to submit our best Techno Commercial Bid in the time provided for bid submission. Therefore, we request you to allow 2 more weeks extension in submission of bid. We hope you will consider our request and allow us for the time extension.	Not agreed, the Date and Time of submission of tender will remain same as given in NIT.	